

80

PRECAST CONCRETE DECK UNIT BRIDGE

Project Number: L-B(B64)-73-97

Project Development Division  
 PLANS OF PROPOSED IMPROVEMENT ON THE  
**SECONDARY ROAD SYSTEM**  
**WOODBURY COUNTY**  
**PRECAST CONCRETE DECK UNIT BRIDGE**  
**PROJECT NO: L-B(B64)--73-97**

Rutland Township On130th Street Sec. 20, T89N, R43W

**UTILITY CONTACTS**

WESTERN IOWA TELEPHONE - 712-870-1230  
WOODBURY COUNTY REC - 712-870-1031

**TRAFFIC CONTROL PLAN**

THIS ROAD WILL BE CLOSED TO THROUGH TRAFFIC DURING CONSTRUCTION. LOCAL TRAFFIC TO ADJACENT PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.06 OF THE CURRENT STANDARD SPECIFICATIONS. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, AND SIGNING INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATIVE CODE (IAC) CHAPTER 130.

ALL SAFETY CLOSURES SHALL BE FURNISHED, ERECTED, MAINTAINED AND REMOVED BY THE CONTRACTOR.

MAINTENANCE OF SIGNS, BARRICADES AND SAFETY CLOSURES AS STATED IN ARTICLE 1107.09 SHALL APPLY ON THIS PROJECT.

ROAD CLOSURES ON THIS PROJECT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE IN ACCORDANCE WITH ROAD STANDARD TC-252. GUARDRAIL INSTALLATION MUST BE COMPLETE BEFORE THE ROAD IS OPENED TO TRAFFIC.

The Iowa Department of Transportation Standard Specifications for Highway and Bridge Construction, series of 2015, plus current Supplemental Specifications and Special Provisions shall apply to construction work on this project.

Plus Current Special Provisions and Supplemental Specifications

THIS PROJECT SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE REQUIREMENTS OF U.S. ARMY CORPS OF ENGINEERS NATIONWIDE PERMIT 14. PERMIT CEMVR-RD-2022-0666. A COPY OF THIS PERMIT IS AVAILABLE FROM THE WOODBURY COUNTY ENGINEERS OFFICE UPON REQUEST. THE U.S. ARMY CORPS OF ENGINEERS RESERVES THE RIGHT TO VISIT THE SITE WITHOUT PRIOR NOTICE. IOWA D.O.T. NOT REQUIRED

**INDEX OF SHEETS**

No.	Description
1	TITLE SHEET
2	LOCATION PLAN
3	ESTIMATE OF QUANTITIES & GENERAL INFORMATION
4	BRIDGE DETAILS
5	BRIDGE WELDING DETAIL & DECK SLAB LAYOUT
6	PROFILE VIEW
7	SITUATION PLAN
8-9	PRECAST UNIT DETAILS

**ROAD STANDARD PLANS**

The following Bridge Standards shall be considered applicable to construction work on this project.

Identification	Date	Identification	Date	Identification	Date
TC-252	04-21-20				

**WOODBURY COUNTY**

PROJECT NO: L-B(B64)-73-97

JUNE 28, 2022

Letting Date

Approved
Board of Supervisors

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

6/7/2022  
 Signature Date

Mark J. Nahra  
 Printed or Typed Name

My license renewal date is December 31, 2022  
 Pages or sheets covered by this seal:  
 Pages 1, thru 9

**IOWA**  
**ONE CALL**  
 1-800-292-8989  
 www.iowaonecall.com