Project Number: RC-CO97(130)--9A-97

PLANNING, PROGRAMMING AND MODAL DIVISION

PLANS OF PROPOSED IMPROVEMENT ON THE

SECONDARY ROAD SYSTEM
WOODBURY COUNTY
P.C.C. PAVEMENT-REPLACE
PROJECT NO: RC-CO97(130)--9A-97

The Iowa Department of Transportation Standard Specifications for Highway, and Bridge Construction, Series 2015, plus applicable General Supplemental Specifications, Developmental Specifications, Supplemental Specifications and Special Provisions, shall apply to construction on this project.

P.C.C. FULL DEPTH PAVING 26'-0'x0'-10" ON PORT NEAL CIRCLE FROM NEAR THE CENTER SEC. 31-87-47 TO NEAR THE E1/4 CORNER NE1/4 SEC. 30-87-47

INDEX OF SHEETS

No.	Description
A1	TITLE SHEET
A2	LOCATION PLAN
B1	QUANTITIES
B2	GENERAL NOTES AND REFERENCE INFORMATION
C1	TYPICAL DETAILS
C2	PAINTED PAVEMENT MARKINGS DETAILS
C3	INTERSECTION DETAILS
D1-D8	PLAN AND PROFILE
V1-V2	TURNING SITUATION PLAN

MILEAGE SUMMARY

Div.	Location	Lin. Ft.	Miles
	STA. 5+33.47 TO STA. 93+61.20	8,827.73	
	TOTAL LENGTH RC-CO97(130)--9A-97	8,827.73	1.672

ROAD STANDARD PLANS

The following Standard Plans shall be considered applicable to construction work on this project.

Identification	Date	Identification	Date	Identification	Date
PM-110	04-16-13	PV-101	04-21-15		
PM-111	04-21-15	PV-106	04-21-15		
PM-120	10-21-14	PV-301	04-19-11		
PM-210	10-18-11	TC-251	04-17-12		
PM-240	04-21-15	TC-252	10-20-15		
PV-10	04-19-11				

TRAFFIC CONTROL PLAN

THIS ROAD WILL BE CLOSED FOR THROUGH TRAFFIC DURING CONSTRUCTION. TRAFFIC ROUTES ADJACENT TO PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.08 OF THE CURRENT STANDARD SPECIFICATIONS. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, SIGNING, AND PAVEMENT MARKINGS INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATION CODE (IAC) CHAPTER 130.

MAINTENANCE OF SIGNS AND BARRICADES AS STATED IN ARTICLE 1107.09 SHALL APPLY ON THIS PROJECT.

SIGNING ON THIS PROJECT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE IN ACCORDANCE WITH ROAD STANDARD TC-251, AND TC-252.

Approved

Board of Supervisors

LICENSED PROFESSIONAL ENGINEER
MARK J. NAHRA
11452
IOWA

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Mark J. Nahra 9/22/2015
Date

Iowa Registration Number 11452
Expiration Date 12/31/2016

Pages or sheets covered by this seal:
Pages A1, A2, B1, B2, C1 thru C3 & D1 thru D8, and V1, V2

2011 AADT 740 V.P.D.

IOWA ONE CALL
1-800-292-8989
www.iowaonecall.com

WOODBURY COUNTY
P.C.C. PAVEMENT-REPLACE
PROJECT NO: RC-CO97(130)--9A-97
Letting Date