

Board Item

1-23-18

13b

P.C.C. OVERLAY

PROJECT NO: STP-S-CO97(134)--5E-97

APRIL 17, 2018

Letting Date

IOWA
DEPARTMENT OF TRANSPORTATION
 Highway Division
 PLANS OF PROPOSED IMPROVEMENT ON THE
FARM TO MARKET SYSTEM
WOODBURY COUNTY
P.C.C. OVERLAY
PROJECT NO. STP-S-CO97(134)--5E-97

Refer to the Proposal Form for List of Applicable Specification

ON D54 FROM INTERSECTION OF D54 AND 1A
31 EAST 5.6 MILES TO JUST EAST OF THE
INTERSECTION OF D54 AND L27

TRAFFIC CONTROL PLAN

ROAD WILL BE CLOSED TO THROUGH TRAFFIC DURING CONSTRUCTION. TRAFFIC ROUTES ADJACENT TO PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.08 OF THE CURRENT STANDARD SPECIFICATIONS. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, SIGNING, AND PAVEMENT MARKINGS INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATION CODE (IAC) CHAPTER 130.

MAINTENANCE OF SIGNS AND BARRICADES AS STATED IN ARTICLE 1107.09 SHALL APPLY ON THIS PROJECT.

SIGNING ON THIS PROJECT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE IN ACCORDANCE WITH ROAD STANDARD TC-252.

Approved
Board of Supervisors

	I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	1/26/2018 Date
	Iowa Registration Number 11452 Expiration Date 12/31/2018
	Pages or sheets covered by this seal: 1 thru 19

2015 AADT290-360 V.P.D.

Project Number: STP-S-CO97(134)--5E-97

INDEX OF SHEETS	
No.	Description
1	TITLE SHEET
2	LOCATION MAP
3	ESTIMATED QUANTITIES AND GENERAL NOTES
4	ESTIMATE REFERENCE INFORMATION
5	TABULATIONS
6	TYPICAL SECTIONS AND DETAILS
7	INTERSECTION LAYOUT
8.-19.	PLAN AND PROFILE

STANDARD PLANS					
The following Standard Plans shall be considered applicable to construction work on this project.					
Identification	Date	Identification	Date	Identification	Date
BA-200	10-18-16	PM-110	04-16-13		
BA-221	04-18-17	PM-120	10-21-14		
BA-225	10-17-17	PV-101	10-17-17		
BA-260	10-18-16	TC-202	04-21-15		
BR-101	04-21-15	TC-213	04-17-12		
BR-104	10-17-17	TC-252	04-19-16		

MILEAGE SUMMARY			
Div.	Location	Lin. Ft.	Miles
	STA. 0+00.00 TO STA. 290+50 DEDUCT FOR BRIDGE STA. 11+32.39 TOTAL LENGTH PROJECT STP-S-CO97(134)--5E-97	29,050.00 -281.67 28,768.33	5.45



WOODBURY COUNTY