



Woodbury County Secondary Roads Department

759 E. Frontage Road • Merville, Iowa 51039
Telephone (712) 279-6484 • (712) 873-3215 • Fax (712) 873-3235

14c

COUNTY ENGINEER
Mark J. Nabra, P.E.
mnabra@sioux-city.org

ASSISTANT TO THE COUNTY ENGINEER
Benjamin T. Kusler, E.I.T.
bkusler@sioux-city.org

SECRETARY
Tish Brice
tbrice@sioux-city.org

Structure: FHWA# 355055
Quote for Bridge Repair
Bridge Located in Section 29 Arlington Township
On Haskell Ave. over McElhaney Creek FEMA SITE 12

	Quantity	Quote	Total
Furnish and drive four (4) 60' HP 12" x 53"	1	Lump Sum @ \$ <u>44,800.00</u>	Lump Sum = <u>44,800.00</u>
Furnish and Place Safety Fence	2	Each @ \$ <u>500.00</u>	Each = <u>1,000.00</u>
Total Quote:			<u>45,800.00</u>

The Lump Sum cost includes: Mobilization, equipment, labor, four (4) new 60' HP 12X 53 steel pile, materials to drive four steel piling and weld onto existing bridge as illustrated on attached diagram. Signing shall be done for the road closure by Woodbury County and the safety fence shall be supplied by the contractor as quoted. The steel piling and welding shall be as per Section 4167 of the I.D.O.T. specifications. The hammer and driving method used for driving piles shall be per section 2501.03. The successful contractor shall supply certification of insurance listing Woodbury County as additionally insured. **ALL WORK SHALL BE COMPLETED BY JULY 13, 2015.** QUOTES ARE DUE BY 4:00 PM April 29, 2015. Quotes shall be mailed to the County Engineer's Office at 759 East Frontage Road Merville, Iowa 51039 and clearly marked in the lower left hand corner "REPAIR QUOTE BRIDGE".

NELSON & ROCK CONTRACTING, INC.

Contractor: 23565 HWY K45
ONAWA, IA 51040

Address: _____

Signature: Wayne L. Rock, Date: 4-29-15



Woodbury County Secondary Roads Department

759 E. Frontage Road • Merville, Iowa 51039
Telephone (712) 279-6484 • (712) 873-3215 • Fax (712) 873-3235

14c

COUNTY ENGINEER
Mark J. Nagra, P.E.
mnagra@sioux-city.org

ASSISTANT TO THE COUNTY ENGINEER
Benjamin T. Kusler, E.I.T.
bkusler@sioux-city.org

SECRETARY
Tish Brice
tbrice@sioux-city.org

Structure: FHWA# 355055
Quote for Bridge Repair
Bridge Located in Section 29 Arlington Township
On Haskell Ave. over McElhaney Creek FEMA SITE 12

	Quantity	Quote	Total
Furnish and drive four (4) 60' HP 12" x 53"	1 Lump Sum	@ \$ <u>35,100.00</u> Lump Sum =	<u>35,100.00</u>
Furnish and Place Safety Fence	2 Each	@ \$ <u>350.00</u> Each =	<u>700.00</u>
Total Quote:			<u>35,800.00</u>

The Lump Sum cost includes: Mobilization, equipment, labor, four (4) new 60' HP 12X 53 steel pile, materials to drive four steel piling and weld onto existing bridge as illustrated on attached diagram. Signing shall be done for the road closure by Woodbury County and the safety fence shall be supplied by the contractor as quoted. The steel piling and welding shall be as per Section 4167 of the I.D.O.T. specifications. The hammer and driving method used for driving piles shall be per section 2501.03. The successful contractor shall supply certification of insurance listing Woodbury County as additionally insured. **ALL WORK SHALL BE COMPLETED BY JULY 13, 2015.** QUOTES ARE DUE BY 4:00 PM April 29, 2015. Quotes shall be mailed to the County Engineer's Office at 759 East Frontage Road Merville, Iowa 51039 and clearly marked in the lower left hand corner "REPAIR QUOTE BRIDGE".

October 30, 2015

Contractor: Dixon Construction Co.
Address: 409 Doltward St.
Correctionville, IA 51016

Signature: David R. Dixon Date: 4/29/15