8C
9/26/23

28 - TOTAL SHEETS

Project Number: FM-CO97(149)--55-97

IOWA
DEPARTMENT OF TRANSPORTATION

Highway Division

PLANS OF PROPOSED IMPROVEMENT ON THE

FARM TO MARKET SYSTEM
WOODBURY COUNTY
P.C.C. PAVING PROJECT
PROJECT NO: FM-CO97(149)--55-97

UTILITY CONTACTS

WESTERN IOWA TELEPHONE . 202 CEDAR STREET
LAWTON, IA. 51030 - 712-944-5711 - ERIN NELSON

WOODBURY COUNTY REC. 1495 HUMBOLT AVE.
MOVILLE, IA. 51039 - 712-873-3125 - NATE BAUER

TRAFFIC CONTROL PLAN

THIS ROAD WILL BE CLOSED TO THROUGH TRAFFIC DURING CONSTRUCTION. LOCAL TRAFFIC TO ADJACENT PROPERTIES WILL BE MAINTAINED AS PROVIDED FOR IN ARTICLE 1107.08 OF THE CURRENT STANDARD SPECIFICATIONS. TRAFFIC CONTROL DEVICES, PROCEDURES, LAYOUTS, AND SIGNING INSTALLED WITHIN THE LIMITS OF THIS PROJECT SHALL CONFORM TO THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS" AS ADOPTED BY THE DEPARTMENT PER 761 OF THE IOWA ADMINISTRATIVE CODE (IAC) CHAPTER 130.

ALL SAFETY CLOSURES SHALL BE FURNISHED, ERECTED, MAINTAINED AND REMOVED BY THE CONTRACTOR.

MAINTENANCE OF SIGNS, BARRICADES AND SAFETY CLOSURES AS STATED IN ARTICLE 1107.09 SHALL APPLY ON THIS PROJECT.

ROAD CLOSURES ON THIS PROJECT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE IN ACCORDANCE WITH ROAD STANDARD TC-252.

REFER TO THE PROPOSAL FORM FOR A LIST OF APPLICABLE SPECIFICATIONS

D50: FROM HIGHWAY 31 TO L27

REFER TO SHEET 2 FOR LOCATION MAP

INDEX OF SHEETS

No.	Description
1	TITLE SHEET
2	LOCATION PLAN
3	ESTIMATE OF QUANTITIES
4	REFERENCE INFORMATION
5	TABULATIONS
6	INTERSECTION DETAILS
7	INTERSECTION DETAILS
8	INTERSECTION SAWCUT DETAILS
9	INTERSECTION SAWCUT DETAILS
10	TYPICAL DETAILS DIVISION I AND DIVISION II
11-21	PLANVIEW DIVISION I AND DIVISION II
22-27	PROFILE DIVISION I
28	PROFILE DIVISION II

MILEAGE SUMMARY

Div.	Location	Lin. Ft.	Miles
	DIVISION I STA. 12+00.00 TO STA. 141+19.00	12,919.00	
	DIVISION II STA. 16+89.52 TO STA. 24+00.00	710.48	
	TOTAL LENGTH PROJECT FM-CO97(143)--55-97	13,629.48	2.581

ROAD STANDARD PLANS

The following Bridge Standards shall be considered applicable to construction work on this project.

Identification	Date	Identification	Date	Identification	Date
BR-101	10-18-22	PM-110	04-21-20		
BR-104	10-17-17	PM-120	10-21-14		
EW-301	04-20-21	PV-10	04-21-20		
SI-173	04-19-16	PV-101	04-19-22		
SI-211	10-18-22	TC-252	04-21-20		

Approved

Board of Supervisors

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Mark J. Nahra 9/26/2023

Signature Date

Mark J. Nahra

Printed or Typed Name

My license renewal date is December 31, 2024
Pages or sheets covered by this seal:
Pages 1, thru 28

LICENSED PROFESSIONAL ENGINEER MARK J. NAHRA 11452 IOWA

IOWA ONE CALL
1-800-292-8989
www.iowaonecall.com
811 Know what's below. Call before you dig.

2019 AADT 30 V.P.D.

WOODBURY COUNTY

P.C.C. PAVING PROJECT

PROJECT NO: FM-CO97(149)--55-97

Letting Date